





Sales - Quote


Ms. Becky Escott
Botus Fleming Parish Council
Lambest Cottage
Menheniot
Liskeard
PL14 3RE

Quote No. SQ269178-1
Sell-to Contact No. 870334
Quote Date 21-03-2022
Expiration Date 20-04-2022

Salesperson Stephen Woodd
E-Mail stewoo@kompan.com
Phone No. 07764 365 666

Project Name EN26996 Hatt Recreation Field

No.	Description	Quantity	Unit of Measure	Unit Price	Amount
New Equipment and its Installation					
<u>KSW904-CUSTOM</u>	KOMPAN Swing Frame, KSW904 Custom Variant 20151495	1	Pieces	4,140.00	4,140.00
					
INSTALLATION	Installation - KSW904-CUSTOM KOMPAN Swing Frame, KSW904 Custom Variant	1	Pieces	1,289.00	1,289.00
<u>PCM159-1001</u>	KOMPAN Wehopper, colour red, inground	1	Pieces	3,340.00	3,340.00
					
INSTALLATION	Installation - PCM159-1001 KOMPAN Wehopper, colour red, inground	1	Pieces	965.75	965.75
<u>FSW20501-0901</u>	KOMPAN Wide Overhead Ladder Pro Inground colour Orange NOTE: order safety sign	1	Pieces	1,730.00	1,730.00
					
INSTALLATION	Installation - FSW20501-0901 KOMPAN Wide Overhead Ladder Pro	1	Pieces	473.63	473.63
<u>M14374-12P</u>	KOMPAN Albatross Spring Seesaw Inground 60cm	1	Pieces	1,760.00	1,760.00
					
INSTALLATION	Installation - M14374-12P KOMPAN Albatross Spring Seesaw	1	Pieces	319.00	319.00

No.	Description	Quantity	Unit of Measure	Unit Price	Amount
M53600-3418P	KOMPAN Toddler Train Inground 60cm 	1	Pieces	2,530.00	2,530.00
INSTALLATION	Installation - M53600-3418P KOMPAN Toddler Train	1	Pieces	250.00	250.00
Safer Surfacing					
EN-MGRA Z3 56	Supply & Install EcoSmart Single Layer Grass Mat (+56m ²) All existing grass to be fully established and well maintained to give a critical fall height.	48	Squ. Metre	33.56	1,610.88
EN-MSHO Z3 56	Supply & Install SmartPlay Grass Mat with Shockpad (+56m ²) Grass mats with foam shockpad beneath - for cortical fall height up to 2.5m (monkey bars)	24	Squ. Metre	76.71	1,841.04
EN-EXC50 DSP	Excavate 50mm Incl. DSP Excavate for shockpad (monkey bars)	24	Squ. Metre	9.32	223.68
EN-SITEWEL U4WK	Site Welfare Under 4 Weeks Portaloo for workforce	1	Pieces	480.14	480.14
EN-SKIP	Skip Hire 8 Cy Mixed Waste (Not Rubber) For removal of spoil and packaging	1	Pieces	487.11	487.11
EN-TELEHANDLER	Telehandler Hire for 1 Week For unloading deliveries and positioning equipment	1	Pieces	842.47	842.47
EN-HERAS	Heras Fencing Unload, Erect & Dismantle	70	Metre	7.37	515.90
EN-HERASMIN	Heras Fencing Delivery & Collection Rate	1	Pieces	150.82	150.82
EN-HERASWK	Heras Fencing Hire Per Week	70	Metre	2.05	143.50
FREIGHT	Freight	1	Pieces	877.50	877.50
Subtotal					23,970.42
Project Discount Amount					-1,818.00
Total GBP Excl. VAT					22,152.42
20% VAT					4,430.48
Total GBP Incl. VAT					26,582.90

Alternative Items

No.	Description	Quantity	Unit of Measure	Unit Price	Amount
EN-FENCE BWTP 1H G	Supply 1m High Playspec Bowtop Fencing Galvanised	67	Metre	48.77	3,267.59
EN-IFENCE 120	Install Fencing < 1.20 m	67	Metre	22.53	1,509.51

Alternative Items

No.	Description	Quantity	Unit of Measure	Unit Price	Amount
EN-GATE COMBI 1H P	Supply 1m High Prosafe Combi Gate Powder Coated Yellow	1	Pieces	1,192.86	1,192.86
EN-GATE DBL 1H G	Supply 1m High Playspec Maintenance Gate Galvanised	1	Pieces	464.29	464.29
EN-IGATE SINGLE	Install Single Gate	1	Pieces	273.97	273.97
EN-IGATE DOUBLE	Install Double Gate	1	Pieces	308.22	308.22
EN-FREIGHT EXTRA	Fence/gate freight charge	245	Pieces	2.20	539.00

Payment Terms

Net 30 days

The colour and surface texture of products and surfacing manufactured with the recycled content are influenced by the differences within the used recycled, raw materials. Therefore, minor differences in the visuality and texture not only occur, but are to be expected.

Please Note our Payment Terms

Please see below the standard payment terms offered by KOMPAN for orders over the value of £5,000. If your project has specific payment criteria, please discuss this with us at the time you place your order.

Public Body & Local Authority Customers - (City/County/District/Borough/Town & Parish Councils)

Invoice 1: 100% of the value of your KOMPAN equipment. Issued on the day of shipment from our factory (Payable within 30 days from date of invoice).

Invoice 2: Remaining value of your project. Issued on completion (Payable within 30 days from date of invoice).

Limited, Private & Public Companies, Sole Traders, Schools & Private Individuals - (PLC, LTD, LLP, Community Interest Co.)

Invoice 1: 100% of the value of your KOMPAN equipment. Issued at point of order. (Payable within 5 days, and PRIOR to manufacture.)

Invoice 2: Remaining value of your project. Issued on completion. (Payable within 30 days from date of invoice).

Please refer to Clause 3 in our Terms & Conditions

Customer responsible for offloading; however KOMPAN can provide a quotation for a Hiab delivery upon request.